

August 12, 2025

Andy Gehrke, PE  
Robert Almanza, EIT  
HECO Engineers  
PO Box 235  
Payette, Idaho 83661

**Re: New Reservoir & Booster Pump Station, Plan Review #136-2022, City of Sumpter,  
PWS ID# 4100845  
Final Approval**

Dear Andy & Robert:

Thank you for your submittal to the Oregon Health Authority's Drinking Water Services confirming the project was completed in accordance with the approved plans. A set of as-built drawings and operation & maintenance documents were provided. The project consisted of constructing a new 360,000-gallon bolted steel reservoir, adding a flow meter to the reservoir's outlet piping, expanding the existing booster pump station, installing related piping, replacing approximately 4200 feet of 8-inch asbestos-cement transmission line with HDPE pipe, and installing new automated-read meters.

**Final approval is granted for the project.**

A tracer study must be conducted to determine the chlorine contact time to use in the daily CT calculations. A plan for the tracer study must be submitted for review prior to conducting the study. If you have any questions or would like this in an alternate format, please feel free to call me at (541) 966-0900 or email at [william.h.goss@oha.oregon.gov](mailto:william.h.goss@oha.oregon.gov).

Sincerely,



William Goss, PE  
Regional Engineer

c: Julie Wray, OHA – Drinking Water Services  
Lyndi Ayers, City of Sumpter  
Levi Tickner (pdf copy only)